ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification.

The attention of the public is invited to the Notification calling for tenders for the work of "Constructing a Pump-House at Hassan Town" published on pages 1222-1224, Part VI of the *Mysore Gazette*, dated 29th July 1937.

The last date for receiving tenders is 17th August 1937.

Abstract Notification.

The attention of the public is invited to the notification calling for the tenders for labour portion of the work for "Laying the Distribution Pipes for Water Supply to Hassan Town" published on pages 1224-1225, Part VI of the *Mysore Gazette*, dated 29th July 1937.

The last date for receiving tenders is 20th August 1937.

Notification dated 2nd August 1937.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 30th August 1937, for labour portion of the work for laying pipes for the Rising main for water-supply to Hassan Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1937.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for labour portion of the work for laying pipes for the Rising main for water-supply to Hassan Town," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Estimate of the approximate quantities for the labour portion of the work for laying pipes for the Rising Main for water supply to Hassan Town.

No.	Items of work	Unit	Quantity
1	Earthwork excavation for laying pipe line and filling with consolidation, etc., complete	C.yd.	2,620
2	Laying and lead jointing 6″ C.I. pipes	Each	450
3	Do 4″ C.I. pipes	,,	274
4	Unloading 6″ and 4″ C.I. pipes from the wagons, carting from Hassan Railway Station to the Workspot and stacking along the proposed line	Cwt.	1,886
5	Constructing valve cisterns	Each	4
6	Fixing 6″ Sluice valves	,,	3
7	Fixing 4″ Sluice valves	,,	2
8	Fixing 6″ and 4″ C.I. bends	,,	5
9	Fixing 6″ Foot bend	,,	1

N. KRISHNIENGAR,
Sanitary Engineer.

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 29th July 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for Metalling and Tarring with Bitumen emulsion to the road alround the Band Stand in Cubbon Park, Bangalore, published in pages 1262-1263, Part VI of *Mysore Gazette*, dated 5th August 1937.

The last date for the receipt of the tender is 13th August 1937.

Abstract Notification dated 29th July 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for Metalling and Tarring the road from the Central Industrial Workshop to High Court and between Central Workshop to Restaurant Road in Cubbon Park, Bangalore, published in pages 1263-1264, Part VI of *Mysore Gazette*, dated 5th August 1937.

The last date for the receipt of the tender is 13th August 1937.

Abstract Notification dated 29th July 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for Metalling and Tarring the road from Sir K. Seshadri Iyer's Memorial Hall to Sydney Road Ookad in Cubbon Park, Bangalore, published in pages 1264-1265, Part VI of *Mysore Gazette*, dated 5th August 1937.

The last date for the receipt of the tender is 13th August 1937.

Abstract Notification dated 30th July 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for extending the Kitchen and side rooms of the Restaurant in Cubbon Park, Bangalore, published in pages 1265-1267, Part VI of *Mysore Gazette*, dated 5th August 1937.

The last date for the receipt of the tender is 20th August 1937.

Abstract Notification dated 2nd August 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for the construction of a Common Club Building for the Mysore Lancers and the Infantry Regiments at Hebbal, Bangalore, published in pages 1267-1269, Part VI of *Mysore Gazette*, dated 5th August 1937.

The last date for the receipt of the tender is 20th August 1937.

Notification dated 5th August 1937.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Buildings Division, up to 20th August 1937, up to 2-30 P.M., for carrying out additions and improvements to Sir K. P. Puttanna Chetty's Out-patient Dispensary in the compound of Victoria Hospital, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 900 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for carrying out Additions and improvements in the compound of Victoria Hospital, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for certain Improvements and Additions to Sir Puttanna Chetty Out-Patient Dispensary in the Compound of Victoria Hospital, Bangalore City.

No.	Items of work	Unit	Rate	Quantity	Cost
	(FOR ONE WING ONLY.)		Rs. a. p.		Rs. a. p.
1	Removing the existing burnt stone slabs, paving alround the building at the portions to be excavated and stacked ..	S.ft.	0 1 0	100	
2	Earthwork excavating foundation and filling in basement including watering and tamping	C.yds.	0 3 6	88	
3	Filling in sand and boulders for loose pockets of foundation including watering and packing, boulders being carted with an average lead of 1½ to 2 furlongs ..	100 C.ft.	7 4 0	313	
4	Burnt granite jelly concrete in lime mortar 1 : 2 : 4 laid in layers of not more than 6" and well consolidated including watering, etc.	,,	0 3 6	980	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs a. p.		Rs. a. p.
5	Burnt size stone in lime mortar with through bond stones 6′ apart for foundation ..	100. C.ft.	0 4 0	829	
6	Do including quions dressing to exposed faces for basement ..	,,	0 5 0	470	
7	Burnt stone slabs 6″ thick exposed portions two line dressed bed and joints one line dressed and laid in lime mortar ..	S.ft.	0 7 6	388	
8	Burnt size stone in lime mortar with through bond stones 6′ apart including quions dressing for the exposed portions of superstructure	C.ft.	0 5 6	1,323	
9	Stone in lime mortar arch work 1½′ deep with through Voussoir and Key stones and one line dressing to intrados and joints	,,	1 10 0	191	
10	Burnt brick in lime mortar for closing, opening in old wall	,,	0 4 0	121	
11	Removing carefully the old existing windows in the waiting room	S.ft.	0 1 0	65	
	(*a*) Removing the existing perforated panel carefully and stacking	,,	0 1 0	32	
12	Constructing masonry pillasters with size stone in lime mortar with intermediate bond stones base and capital slabs, etc., with quion dressing	C.ft.	1 0 0	61	
13	Preparing, hoisting and fixing cut stone pillars 8½′ high with shafts 12″ Dia. stone base and capital with Stucco work as per existing pattern	Each	40 0 0	12	
14	Supplying, hoisting and fixing Tata's Tested R.S. beams and joints	Cwts.	14 0 0	61·14	
15	Roofing with R.C.C. 1 : 2 : 4 as per design with ceiling plaster at bottom and top finish with 3″ surki, two courses of flat tiles and lime mortar plastered ..	Sqr.	85 0 0	11·87	
16	New teakwood windows 4″×5″ frames with glazed shutters in four leaves, bottom glasses being pin headed ones and top ⅛″ ordinary glass with all necessary brass fitting, etc., complete	S.ft.	1 12 0	167	
17	Re-fixing old released windows with its shutters after necessary repairs ..	,,	0 2 6	56	
18	New teakwood doors 4″×5″ frame with shutters 1½″ thick fully panelled as per existing pattern and with all necessary brass fittings	,,	2 0 0	64	
19	Plastering with lime mortar, three coats over stone wall after chiseling the joints of cement pointing on the outer wall of waiting hall	Sqr.	5 0 0	16·68	
20	Flooring with cement concrete 1 : 2 : 4, 1½″ thick over 3″ lime mortar concrete and top finished with ½″ red cement plaster.	,,	23 0 0	7·76	
21	Flooring with 1½″ thick Kadapa Slabs over 3″ lime mortar concrete with neat clear joints and finished with cement pointing with cut lines (slabs laid diagonally) ..	,,	22 0 0	2·55	
22	Cement pointing to stone wall with neat clear joints with cut lines	,,	4 0 0	14·51	
23	Dismantling cornice, carting debries ..	R.ft.	0 1 0	40	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
24	Heavy cornice 2′ deep and 1½′ projection as per existing pattern giving offsets in stone masonry and plastering with cement finish to the required shape with necessary stucco work	R.ft.	1 2 0	125	
25	Dismantling stone masonry parapet wall and carting debris	C.ft.	0 1 0	150	
	(a) Heavy parapet wall with stone in lime mortar 2′×1½′ with 4″ coping slab with chamfered edge at top, blocking course at bottom and finished with cement pointing with cut lines	R.ft.	1 8 0	125	
26	Painting doors and windows with silver grey silicate paint	Sqr.	4 8 0	4.94	
27	Boxing girders with brick-bats and cement mortar plastered with lime mortar and finished with white wash	C ft.	0 12 0	95	
28	Zinc rain water spouts 3″ Dia. and 16′ long including fixing, etc., complete ..	No.	6 0 0	8	
29	Cut stone stops 1′ wide 6″ thick with necessary over-lapping fixed in lime mortar ..	S.ft.	0 10 0	84	
30	White-washing interior, two coats ..	Sqr.	0 4 0	16.68	
31	Paving with old burnt stone slabs alround including cement pointing	S.ft.	0 1 6	100	
	(a) Do with new slabs ..	„	0 6 0	120	
32	Two-line dressing to sides of doors and windows	S.ft.	0 3 0	136	
33	Cement concrete for hold-fasts of doors and windows	L.S.	..	..	

The quantities noted above are for are wing only but tenders should be given for two wings.

Abstract estimate for Extending the Minor Operation Theatre and the Dressing Room in Sir Puttanna Chetty Out-Patient Dispensary in the Compound of Victoria Hospital, Bangalore City.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
	(FOR ONE WING ONLY.)				
1	Removing doors and windows carefully and stacking	S.ft.	0 1 0	88	
2	Dismantling heavy cornice and clearing debris	R.ft.	0 1 0	33	
3	Dismantling stone masonry parapet wall and clearing debris	C.ft.	0 1 0	124	
4	Removing and stacking zinc rain water-spouts	R.ft.	0 1 0	50	
5	Dismantling Madras terrace roof	Sqr.	2 0 0	2.34	
6	Removing and stacking teakwood joists ..	R.ft.	0 0 6	234	
7	Removing and stacking R.S. Beams ..	„	0 2 0	12	
8	Do existing burnt stone paving slab	S.ft.	0 1 0	70	
9	Removing and stacking cills and lintles of windows	„	0 1 0	30	
10	Dismantling stone masonry and carting debris	C.ft.	0 0 9	295	
11	Earthwork excavating foundation and filling in basement including watering and consolidating	C.yd.	0 3 6	25	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
12	Filling in loose pockets of foundation with boulders and sand including watering and packing	100 C.ft.	7 4 0	144	
13	Burnt granite jelly in lime mortar concrete 1 : 2 : 4 laid in layers of not more than 6" well consolidated	C.ft.	0 3 6	234	
14	Burnt size stone in lime mortar with through bond stones 6' apart with neat clear joints for foundation	,,	0 4 0	301	
15	Do for basement with quoins dressing to all exposed quoins ..	,,	0 5 0	119	
16	Burnt stone slabs 6" thick exposed faces, two-line dressed bed and joints one line dressed and laid over lime mortar with neat clear joints	S.ft.	0 7 6	124	
17	Filling in the inner yard of the extended portion with earth conveyed	C.yds.	0 6 0	14	
18	Burnt size stone in lime mortar with through bond stones 6' apart and dressing all exposed quoins for superstructure ..	C.ft.	0 6 0	916	
19	Burnt stone arch work with through Voussoirs and key stones with two line dressing, intrados etc., complete	,,	1 12 0	21	
20	Refixing old doors and windows with necessary repairs	S.ft.	0 2 6	88	
21	New teakwood door with 3½" ×5" frame with shutters 1½" thick fully panelled as per existing pattern with all-brass fittings complete	,,	2 0 0	64	
22	Preparing and fixing new teakwood glazed ventilators with semi-circular frame ..	,,	1 12 0	11	
23	Supplying and fixing Tata's Tested rolled steel beams and joists as per British Standard specifications	Cwts.	14 0 0	9·64	
24	Fixing old teakwood joists with necessary repairs	R.ft.	0 0 6	234	
25	New teakwood wrought and put up ..	C.ft.	4 8 0	29	
26	Roofing with pucca terrace with ceiling plaster at bottom and roof, finish at top as per specifications	Sqr.	45 0 0	468	
27	Plastering with lime mortar, three coats over stone wall	,,	5 0 0	10·25	
28	Flooring with 1st class Kadappa slab 1½" thick cut diagonally laid in lime mortar concrete and finished with cement pointing with cut lines	,,	22 0 0	1·84	
29	Heavy cornice 2' deep and 1½' porjection as per existing pattern giving offsets in stone masonry and plastering with cement and finished to shape	R.ft.	1 2 0	40	
30	Heavy parapet wall with stone in lime mortar 1½' ×2' with blocking course at bottom and 4" coping slab at top with chamfered edges, etc., as per design and pattern with cement pointing with cut lines	,,	1 8 0	40	
31	Painting doors and windows with two coats of silver grey silicate paint	Sqr.	4 8 0	5·75	
32	Boxing girders with terrace bricks in cement mortar and finished with lime mortar plastering and white-washing..	C.ft.	0 12 0	14	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
33	Cement pointing to stone masonry with white mixed cement including cut lines.	Sqr.	3 0 0	5.37	
34	Zinc rain water-spouts 3" Dia. and 15' long including fixing	Each	4 0 0	6	
35	White-washing interior, two coats ..	Sqr.	0 4 0	10.25	
36	Paving with old burnt stone slabs alround including cement pointing	S.ft.	0 1 6	70	
37	Two-line dressing to stone masonry to the sides of windows	„	0 4 0	30	
38	Cement concrete hold-fasts of doors and windows	L.S.	..	..	

The quantities noted aboveare for one wing only but tenders should be given for two wings.

B. R. GARUDACHAR,
Executive Engineer.

MEDICAL DEPARTMENT

MENTAL HOSPITAL, BANGALORE CITY.

Abstract Notification dated 9th Agust 1937.

Scaled tenders in triplicate for the supply of :—

1. Bedding and Clothing to New Mental Hospital,
2. Bedding and Clothing to Old Mental Hospital,
3. Weaving Materials to Old Mental Hospital,

will be received by the undersigned on Monday the 6th September 1937 at 11 A.M. For particulars, please see pages 1272 to 1275 of Part VI of the *Mysore Gazette*, dated 5th August 1937.

M. V. GOVINDASWAMI,
Superintendent.

SRI NARASIMHARAJA HOSPITAL, KOLAR.

Abstract Notification.

Sealed tenders for the supply of Bedding and Clothing for the use of this Hospital for the year 1937 will be received by the District Medical Officer, Kolar, on 14th August 1937 at 11 A.M. at the District Hospital, Kolar. For further particulars, *vide Mysore Gazette*, dated 29th July 1937, pages 1227-1228, Part VI.

N. A. IYENGAR,
District Medical Officer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE SUPERINTENDENT, CENTRAL INDUSTRIAL WORKSHOP, BANGALORE.

Notice dated 4th August 1937.

Sealed tenders will be received at the office of the Superintendent, Government Central Industrial Workshop, Bangalore, up to 3 O'clock on Monday the 16th August 1937, from contractors who are willing to supply the following articles during the year 1937-38. The approximate quantities required are noted against the items :—

1. Red earth about 100 carts, each cart to weigh net. 15 cwts.
2. White river sand about 100 carts, each cart to weigh 15 cwts.
3. Lime stone, unburnt, about 30 tons.
4. Jungle-wood charcoal—only big lumps are required about 15 tons.
5. Straw, ragi, about 1,000 bundles, each bundle to weigh 30 lbs. net.
6. Clay about 50 carts, each cart to weigh net 15 cwts.
7. Yellow loamsand about 100 carts for the use of Foundry bedding.